



AMENDMENT OF WORK ORDER

To, M/s C.T.C Comapny Vill-Asuvala, Post-Maharajampur, Tehsil- Dhanaura, Amroha, Uttar Pradesh- 244231 Vendor's Details :- Reference Number : WV-C 1374 Contact Person : Mr. Gaurav Choudhary Email: ctcindia1987@gmail.com Phone No : (+91) 9990552606, 9286626220 GSTIN No. : 09AJXPH2601N1ZQ	WO No. : PNC/JJM/UP/BAH-5B/2023-24/0859-R1 Date : 03-08-2024 Amendment No. - 01 Employer's Details :- Contact Person : Mr. JS Mishra (GM) : Mr. Rakesh Tiwari (PM) Email-ID : gmwp@pncinfratech.com : pmbahwp@pncinfratech.com Phone No. : (+91) 9267933270, (+91) 9859939901
Billing Address : PNC Infratech Limited PNC Tower 3/22-D, Civil Lines ,By Pass Road NH2, Agra, Uttar Pradesh 282002 GSTIN: 09AACCPO377Q1ZU	Consignee Address: PNC Infratech Limited Near Mahima Mahila Inter College, Lucky Petrol Pump, Bahraich-Huzoorpur Rd Dist. from Bahraich 05KM. Sukhnaidya-Bahraich, Uttar Pradesh-271801

Sub: Work Order for Railway Crossing for laying of pipeline in in the state of Uttar Pradesh under the Jal Jeevan Mission for **Bahraich District in Devipatan Division.**

Reference: 1. Our Work Order No.: PNC/JJM/UP/BAH-5B/2023-24/0859; Dated: 17-01-2024

Dear Sir,

With reference to the discussion held with you, we are pleased to issue this Work Order to carryout **"Pipe laying work by trenchless method for crossing of Railway ROW "** for the above referred project as detailed below :-

S. No.	Description	HSN/ SAC Code	UOM	Rate in INR	PNC/JJM/UP/BAH-5B/2023-24/0859 Dated 17-01-2024		PNC/JJM/UP/BAH-5B/2023-24/0859-R1 Dated 03-08-2024		
					Approx. Quantity	Amount in INR	Approx. Quantity	Amount in INR	
					Existing Work Order		Amendment WO		
1	Trenchless crossings- Survey, site Investigation, planning , Design & Drawings as per Railway/NH/State Road manual and vetting/checking/ approval from concerned authority and taking NOC for trenchless crossing of National highway road and/or Railway track (crossing length as per site requirements and as approved by concerned authority), for required diameter of Rising main/ distribution pipe including supply and laying of required size of MS casing pipe per (as per IS:3589 & made from material confirming to IS:2062) with 750 Micron PU coating internally and 250 micron anti corrosive bituminous paint externally by trenchless technology method at an average depth 3.60 mtr from normal ground level up to top of casing pipe, excavation & filling of Pit, Dewatering arrangement, shoring/ shuttering/ Supporting system for soil, fixing of two nos. ISI Marked Sluice valve, one on each side of crossing, construction of sluice valve chambers, testing of pipelines as directed by concerned authority etc. and disposal of surplus materials etc. all complete work including laying of carrier pipe inside casing pipe, as per specification given in the bid documents including supply of all materials, labour T&P etc. for proper completion of work as per instruction of Engineer. NOTE: (Only HDPE/DI pipes and fittings and sluice valves will be provided by PNC on FOC basis at PNC Store, GI pipes and fittings if required shall be supplied by the agency at no additional cost) (Casing pipe/Carrier pipe should be as per RDSO guideline)								
1.1	Survey, investigation, drawings and issuance of NOC for work of railway crossing								





PNC Infratech Limited

An ISO 9001 : 2015 Certified Company

WO No : PNC/JJM/UP/BAH-5B/2023-24/0859-R1, Dated: 03-08-2024

S. No.	Description	HSN/ SAC Code	UOM	Rate in INR	PNC/JJM/UP/BAH-5B/2023-24/0859 Dated 17-01-2024		PNC/JJM/UP/BAH-5B/2023-24/0859-R1 Dated 03-08-2024	
					Approx. Quantity	Amount in INR	Approx. Quantity	Amount in INR
					Existing Work Order		Amendment WO	
1.2	Execution of Railway Line crossing (all casing pipes up to 350 mm diameter)		RMT					
Sub Total								
State GST 9 %								
Central GST 9 %								
Grand Total								
In Word (As Per Amendment)								
Note: The quantities indicated above are approximate and payment shall be made for the actual quantities executed and certified by Engineer in Charge. You need to submit detailed measurement sheets along with documentary proof for respective BOQ items in corresponding units of measurement.								

TERMS AND CONDITIONS:-

1) General

- a) This work order is for railway crossings at locations as listed below:

S.N	Scheme Name	Block	DIA OF CARRYING PIPE (MM)	Railway Pillar No.	RAILWAY CROSSING ACTUAL LENGTH (M)
1	Suhalwa	Payagpur	125	30/7-30/8	54
2	Chaisar	Payagpur	125	27/17-29/1	42
3	Jhala tarhar	Payagpur	125	36/10-36/11	48
4	Sarsa-1	Payagpur	125	44/4-44/5	60
5	Madhangra	Payagpur	160	39/15-39/16	60
6	Kaanchar Katorwa	Vishweshwarganj	110	25/4-25/5	54
7	Kaanchar	Vishweshwarganj	160	25/4-25/5	54
8	Sarsa-2	Payagpur	63	43/1-42/15	72
9	Itkauri	Chittaura	125	72/7-72/8	120
10	Unnaisa	Chittaura	160	50/1-50/2	54
11	Khalimpur	Chittaura	160	53/8-53/9	60
12	Aminpur Ngraur	Chittaura	160	57/8-57/9	48
13	Rasulpur Sariya	Chittaura	63	52/5-52/6	54
14	Raghunathpur	Risiya	120	89/8-89/9	72
15	Bargawan	Risiya	125	81/1-81/2	66

- b) Sub-contractor should depute following listed items/Machineries dedicated to this project site and make sure to keep everything in proper working condition:- HDD Machines, JCB/ Tipper/ Tractors, Crane, Polymer/ Bentonite slurry blending set up with required storage tanks, Engineers, technicians, skilled and unskilled labours- As required.



Corporate Office : PNC Tower,
3/22-D, Civil Lines, Bypass Road,
NH-2, Agra-282002

Regd. Office : NBCC Plaza, Tower II,
4th Floor, Pushp Vihar, Sector-V, Saket
New Delhi-110017 (India)

Tel. : 91-562-4054400 (30 Lines)
91-562-4070000 (30 Lines)

Fax : 91-562-4070011


Email : ho@pncinfratech.com

Page 2 of 4

Tel. : 91-11-29574800 (10 Lines)
91-11-29566511, 64724122

Fax : +91-11-29563844

Email : delhioffice@pncinfratech.com
Web. : www.pncinfratech.com
CIN : L45201DL1999PLC195937



COMPLETION CERTIFICATE

This is certified that the work of laying of M.S Casing pipe to pass HDPE Carrier water pipe line under Railway track of North Eastern Railway Lucknow division has been completed successfully including hydro testing by Trenchless technique (H.D.D Method) without any loss to the Railway property by PNC Infratech Limited, on behalf of Executive Engineer (Rural), U.P. Jal Nigam District- Bahraich Uttar Pradesh.

S.N	Scheme Name	Application ID	At Km.	B/w Rly Stn.	MS Casing Ø	HDPE Carrier Ø	Completion Date
1	Unnaisa	WL-113	50/1-50/2	CLW-BRK	300	150	26-10-2024
2	Aminpur Ngraur	WL-124	57/8-57/9	CLW-BRK	300	150	10-11-2024

15-01-25
सीनियर सेक्शन इंजी/पी०व०
Senior Section Eng./P.way
पू०उ०रे०/N E. Rly.
बहराइच/Bahraich




COMPLETION CERTIFICATE

This is certified that the work of laying of M.S Casing pipe to pass HDPE Carrier water pipe line under Railway track of North Eastern Railway Lucknow division has been completed successfully including hydro testing by Trenchless technique (H.D.D Method) without any loss to the Railway property by PNC Infratech Limited, on behalf of Executive Engineer (Rural), U.P. Jal Nigam District- Bahraich Uttar Pradesh.

S.N	Scheme Name	Application ID	At Km.	B/w Rly Stn.	MS Casing Ø	HDPE Carrier Ø	Completion Date
1	Itkauri	WL-112	72/7-72/8	BRK-RS	300	125	23-12-2024
2	Raghunathpur	WL-122	89/8-89/9	MT-NNP	300	120	27-12-2024

only 89/8-89/9
16-01-25
सीनियर सेक्शन इंजीनियर/पी.वे.
Senior Section Engineer/P.W
पूर्वोत्तर रेलवे नानपारा
N.E.Railway Nanpara

only 72/7-72/8
15-01-25
सीनियर सेक्शन इंजी/पी.वे.
Senior Section Eng./P.way
पूर्वोत्तर रेलवे/ N E. Rly.
बहराइच/ Bahraich



COMPLETION CERTIFICATE

This is certified that the work of laying of M.S Casing pipe to pass HDPE Carrier water pipe line under Railway track of North Eastern Railway Lucknow division has been completed successfully including hydro testing by Trenchless technique (H.D.D Method) without any loss to the Railway property by PNC Infratech Limited, on behalf of Executive Engineer (Rural), U.P. Jal Nigam District- Bahraich Uttar Pradesh.

S.N	Scheme Name	Application ID	At Km.	B/w Rly Stn.	MS Casing Ø	HDPE Carrier Ø	Completion Date
1	Jhala Tarhar	WL-115	36/10-36/11	PDR-YEAM	300	125	20-11-2024
2	Sarsa-1	WL-116	44/4-44/5	YEAM-CLW	300	125	23-11-2024
3	Madhangra	WL-117	39/15-39/16	YEAM-PDR	300	160	28-11-2024
4	Kaanchar	WL-118	25/4-25/5	BGAN-BEU	250	110	10-12-2024
5	Kaanchar Katorwa	WL-119	25/4-25/5	BGAN-BEU	300	160	03-12-2024
6	Sarsa-2	WL-120	43/1-42/15	YEAM-CLW	250	63	17-12-2024
7	Suhaiwa	WL-110	30/7-30/8	BEU-PDR	300	125	03-01-2025
8	Chaisar	WL-111	27/17-28/1	BEU-PDR	300	125	07-01-2025

15-01-25
सीनियर सेक्शन इंजी/पी०व०
Senior Section Eng./P.way
पू०उ०रे०/N E. Rly.
बहराइच/Bahraich